Beiler's Construction

2984 E 660 N Marshall, IN 47859 7651666

JOB WORK ORDER

DATE OF ORDER 655-3059 STARTING DATE MECHANIC HELPER PHONE CUSTOMER'S ORDER NO. ORDER TAKEN BY BILL TO AY WORK ADDRESS CONTRACT EXTRA CITY JOB NAME AND LOCATION JOB PHONE DESCRIPTION OF WORK TOTAL MATERIALS TOTAL LABOR TAX \$ TOTAL AMOUNT WORK ORDERED BY DATE COMPLETED ☐ Total billing to ☐ Total amount due ☐ No one home be mailed after for above work: or completion of work Signature

I hereby acknowledge the satisfactory completion of the above described work.

Prepared For

Lisa Vitaniemi Thorntown Park (217) 474-3004

DW Remodeling LLC

Estimate #

302

P.O. Box 121

Date

08/15/2022

Lebanon, Indiana 46052

PO#

Thorntown Park- Shelter

Phone: (317) 716-3967

Email: david@dwremodelingllc.com

Description	Rate	Quantity	Total	
Thorntown Park- Shelter House	\$12,100.00	1	\$12,100.00	
Provide & install grey metal over wood siding on outside of bathrooms Provide & install 1X2 wood spacers for shelter roof Provide & install blue metal over existing shingles on shelter roof (approx 50' x 16'- 2 sides)				

Subtotal	\$12,100.00
Total	\$12,100.00

Notes:

Based on current material prices. Price may change with material price fluctuations.

Lisa Vitaniemi



WHITESTONE CONSTRUCTION CORP.

Client: Property: Lisa Vitaniemi

700 S Pearl St

Thorntown, IN 46071

Operator:

WHITESTO

Estimator:

David Roberts

Position:

Project Manager

Company:

Whitestone Construction Corp.

Reference:

Chris White

Position:

DOO

Company:

Whitestone Construction Corp.

Business:

6525 Ferguson St

Indianapolis, IN 46220

Type of Estimate:

Other

Date Entered:

8/2/2022

Date Assigned: 8/1/2022

Home: (217) 474-3004

com

com

(317) 410-8234

(317) 965-0215

whitestone.david113@gmail.

chris.white@whitestone-indy.

Business:

E-mail:

Cellular:

E-mail:

Price List:

ININ8X JUL22

Labor Efficiency:

Restoration/Service/Remodel

Estimate:

TOMJOHNSONPARK700

File Number:

TOMJOHNSONPARK700

Hello,

First and foremost, we at Whitestone would like to extend our gratitude in giving us the opportunity to work with you on this project and look forward to building a lasting relationship for the future!

Please review this proposal and don't hesitate to contact me with any questions or concerns.

Best regards,

David Roberts Sales/Project Management Whitestone Construction Corp. whitestone.david113@gmail.com (317)410-8234





TOMJOHNSONPARK700

Shelter Roof

DESCRIPTION	QTY	REMOVE	REPLACE	TAX	TOTAL
1. Tear off, haul and dispose of comp. shingles - Laminated	16.00 SQ	61.80	0.00	0.00	988.80
2. Eave trim for metal roofing - 26 gauge	132.00 LF	0.00	5.25	19.96	712.96
3. Roofing felt - 30 lb.	16.00 SQ	0.00	36.02	14.52	590.84
4. Ridge cap - metal roofing	50.00 LF	0.00	5.32	7.81	273.81
5. Gable trim for metal roofing - 26 gauge	70.00 LF	0.00	5.62	12.40	405.80
6. Drip edge/gutter apron	110.00 LF	0.00	2.68	9.39	304.19
7. Closure strips for metal roofing - inside and/or outside	110.00 LF	0.00	1.85	3.93	207.43
8. Metal roofing	1,760.00 SF	0.00	11.27	595.06	20,430.26
Totals: Shelter Roof			10 E 10000 S 3000 S 2000 S	663.07	23,914.09

Restroom Exterior

DESCRIPTION	QTY	REMOVE	REPLACE	TAX	TOTAL
9. Eave trim for metal roofing - 26 gauge	25.00 LF	0.00	5.25	3.78	135.03
10. Closure strips for metal roofing - inside and/or outside	71.50 LF	0.00	1.85	2.55	134.83
11. Metal roofing - For Siding	445.00 SF	0.00	11.27	150.45	5,165.60
12. House wrap (air/moisture barrier)	445.00 SF	0.00	0.34	5.92	157.22
Totals: Restroom Exterior				162.70	5,592.68

Labor Minimums Applied

DESCRIPTION	QTY	REMOVE	REPLACE	TAX	TOTAL
13. Siding labor minimum	1.00 EA	0.00	158.48	0.00	158.48
Totals: Labor Minimums Applied				0.00	158.48
Line Item Totals: TOMJOHNSONPARK700				825.77	29,665.25

TOMJOHNSONPARK700 8/5/2022 Page: 2



WHITESTONE CONSTRUCTION CORP.

Summary

Line Item Total		28,839.48
Material Sales Tax		825.77
Replacement Cost Value		\$29,665.25
Net Claim		\$29,665.25
	David Bakarta	
	David Roberts	
	Project Manager	

Please review our proposal and call David Roberts at 317-410-8234 with any questions or concerns. Thank You.

TOMJOHNSONPARK700 8/5/2022 Page: 3